



REQUEST FOR BIDS

Hall Road Drainage Improvement Project - DR-4232-0072

RFB 25BCP08A

September 30, 2025

ADDENDUM #2

Notice to Respondents:

This addendum will be considered a part of Bastrop County's Request for Bids for Hall Road Drainage Improvement Project - DR-4232-0072. Where provisions of this addendum differ from those of the original Request for Bids, this addendum will govern.

ACKNOWLEDGED

Printed Name of Respondent

Authorized Signature

Date

RETURN ONE COPY SIGNED COPY OF THIS ADDENDUM TO THE PURCHASING OFFICE WITH YOUR SEALED BID. FAILURE TO DO SO, MAY AUTOMATICALLY DISQUALIFY YOUR RESPONSE FROM CONSIDERATION FOR AWARD.

ITEMS FOR ADDENDUM #2:

Q: Addendum 1 is erroneous, surrounding the culvert dimensions. There are never any extensions necessary to skew a culvert. If Bastrop County is certain of the overall dimensions (out to out) of the headwall to headwall 26'. The 45-degree skewed culvert is 37' (+/-) of 2-8'x6' culvert.

A: The extensions are only applicable if the contractor proposes pre-cast concrete box culverts. The total overall length as stated in the bid sheet quantities is 74 linear feet.

Q: Is Bastrop County certain a 12' headwall is long enough? 12' only allows for a (+/-) 1.8:1 slope at 6.67' tall.

A: 12ft long headwalls are correct. Bastrop County is aware of the slope and FEMA has approved of this project scope.

Q: The downstream fence is approximate, and dimensions are called for the rip rap to stop at the fence. Please give dimensions of the upstream rip rap limits.

A: The project estimate assumes a 50ft ROW and the rip rap estimate is 60 tons. The project will be paid for using a lump sum total, but Bastrop County will pay Contractor for documented overage of rip rap placed.